# RAIL BALTICA MAIN LINE CONSTRUCTION IN LATVIA











#### PRESENTATION OVERVIEW

- EDZL as Implementing Body in Latvia;
- Rail Baltica Project Governance main stakeholders, structure and financing arrangements;
- Construction procurement process and tender schedule;
- Construction procurement scope sections overview;
- Planned construction schedule key dates;
- Contracts overview FIDIC, pricing basis, payment procedure, bill of quantity extract example;
- Project processes provided by employer;
- Technical scope overview example of bridge structures, embankment, etc.

# ABOUT WORK PROGRESS IN EDZL MANAGED CONSTRUCTION OBJECTS

Link to video: https://youtu.be/5dTccDZXYYo




# PROJECT ORGANISATIONAL STRUCTURE AND FINANCING

#### **Kaspars Vingris**

Head of the Management Board



#### SIA EIROPAS DZELZCELA LINIJAS



#### Members of board:


Kaspars Vingris Tālis Laizāns

#### **Established:**

By Ministry of Transport in October 15th, 2014


#### Share capital

EUR 4 445 400






#### **EDZL ROLE AND RESPONSIBILITIES**



- 1. Implementation of project by:
- Design and construction of point type objects;
- Construction of main line;
- Organization of land acquisition;
- 2. Establishment of infrastructure management system in cooperation with other Baltic states
- 3. Shareholding of Joint Venture

#### Rail Baltica Governance structure





#### PROJECT FINANCING

Beneficiary

Ministry of Transport of the Republic of Latvia AVERAGE 85%
OF NEEDED FINANCING

REMAINING 15% FROM STATE BUDGET



EUROPEAN CLIMATE, INFRASTRUCTURE AND ENVIRONMENT EXECUTIVE AGENCY

The Connecting Europe Facility for Transport Fund

Implementing Body

Eiropas Dzelzceļa līnijas SIA **GA**: Grant Agreements are signed between 3 Beneficiaries

and CINEA (European Climate, Infrastructure and

Environment Executive Agency).

**CEF:** Connecting Europe Facility: object of GA.

MFF: Multi annual Financing Frameworks:

plan of financing object of several Agreements.



#### STRUCTURE OF RAIL BALTICA FINANCING

#### CINEA FINANCING

- The implementation of the Rail Baltica project is financed by co-funding from the European Union up to 85% of the total eligible costs and from national state Budgets Estonia, Latvia and Lithuania. EU financing is included in framework of the Connecting Europe Facility (CEF) funding instrument.
- Generally financing of each activity is forecasted between 81 85% for CINEA and 15% 19% for Beneficiary (State).
- Compensation, time and description of related activities to be performed are fixed at signing of each Grant Agreement signed between Beneficiary and CINEA (5 Grant Agreements signed till now).
- Each Grant Agreement is based on a project application to be prepared by Beneficiary following input of coordinator and Implementing bodies and evaluated by CINEA mostly on the basis of maturity of project and specific criteria defined in Call.



#### STRUCTURE OF RAIL BALTICA FINANCING

#### STATE FINANCING

- State contribution is included in State budget of each year and already reserved.
- VAT is financed by the state but does not impact the Budget (actually in Latvia on construction Reverse Tax VAT is applied).
- The Ministry of Transport by law is not a VAT taxable person The Ministry shall transfer VAT directly to the State budget as a non-eligible cost, VAT is fully financed from the state budget.
- The invoices are paid to the Contractor by the Beneficiary Ministry of Transport of Latvia on base of instruction received from Implementing Body (the contracting authority).



# RAIL BALTICA GLOBAL PROJECT NEED-TO-KNOWS'

#### **Girts Bramans**

Head of Strategic stakeholders and Communications Rail Baltica joint venture RB Rail AS

#### Helsinki Rail Baltica 870 km greenfield railway infrastructure Tallinn 1435 mm Double Pärnu Pärnu track Rīga Central ERTMS Level 2 + FRMCS\* Salaspils Rīga Airport Electrified High Speed 2x25kV AC Night Train Panėvežys Freight Panėvežys Maximum length of + Regional freight trains: 1050m **Vilnius** Kaunas Kaunas Axle load 25t Warszawa Warszawa Design speed: Hamburg \_ 249 km/h for passenger Berlin trains 120 km/h for freight trains Rotterdam • SE-C (Swedish) Duisburg . loading gauge Wien 🕳 Antwerpen ...

Milano

<sup>\*</sup> Subject to confirmation

#### **Rail Baltica Procurement Types**



Contracting authority RB Rail AS

- Global project studies
- Design of main line
- Common Standards
- Business Development
- Marketing & Branding



Contracting authority RB Rail AS on behalf of BEN and IB

- Sub-systems (CCS&ENE)
- Raw Materials and Key Components
- Cross-border Mainline Sections



Contracting authority Implementing bodies (IB)

- Mainline Construction
- Major Engineering Structures
- Local Facilities (including terminals)






#### **Rail Baltica Procurement Governance**



www.railbaltica.org



www.railbaltica.org/pr ocurement/procureme nt-regulation-suppliergualification/







Procurement ID No.	Title	Announced	Updated	Submission Date	Language	
	Invitation to consultation with interested suppliers for procurement procedure "Rail Baltica mainline construction in Latvia"					
RBR 2021/21	Global Project Cost Benefit Analysis (CBA) and Long Term Business Plan	26.08.2021	26.08.2021	30.09.2021		
RBR 2021/18	Data center services	11.08.2021	26.08.2021	07.09.2021	=	
RBR 2021/16	Railways tunnels expert services	11.08.2021	02.09.2021	02.09.2021		
RBR 2021/15	Competitive procedure with negotiations "Consolidated supply of rails for Rail Baltica railway construction"	09.08.2021	01.09.2021	23.09.2021		


#### **Consolidated Procurement of Components/Elements**

**Scope**: 8 types of construction materials incl. cable troughs (cable ducts, cable channels and manholes), rails, turnouts, sleepers and fastening systems, ballast, standardized small concrete elements (e.g. culverts, bridge logos), noise barriers, fencing and other rail infrastructure elements (e.g. rail expansion joints, buffer stops etc.)

All procurements to be launched 2021 under Latvian Public Procurement Law. Tenders for cable troughs, sleepers and fastening systems, turnouts and expansion joints and rails already started. Next week publication of tender for supply or railway ballast planned.

Supply/delivery phase under specifically developed Framework agreement providing access to materials based on contractor call-offs.


**Future IMF's (2 per each country) likely to be used as material storage bases.** Initial stockpiling of key superstructure materials will be ensured, further stock replenishment - responsibility of the superstructure construction company





ADIF, the Administrator of Railway Infrastructure in Spain

#### **BIM** requirements







#### **Construction stage**

Native BIM model with attribute data -> IFC -> Asset Register

#### **BIM** attributes






Client's DMS for information exchange and management

#### **Asset Register database**



ArcGIS platform



Designer

Contractor



# MAIN LINE CONSTRUCTION WORKS PROCUREMENT

#### Einārs Jaunzems

Head of Project implementing department



## EXPECTED STRUCTURE OF PROCUREMENT PROCEDURE

The procurement procedure will be organised in accordance with the regulatory enactments of the Republic of Latvia EU procurement regulation and Latvian Procurement law.

Procurement commission will choose between most common procedures (in past generally competitive procedure with negotiation according to the Article 8, Paragraph Six, Point 3 of the Public Procurement Law).

The procedure consists of two stages:

- The first stage selection of candidates;
- The second stage evaluation of the bids submitted by candidates which will be invited to submit an initial bid and award of rights to conclude a contract.

The second stage may include negotiations that may be relevant to be undertaken as specified by the Contracting Authority. The procurement commission shall be entitled to make a decision not to organise negotiations and award the contract on the basis of the initial bids submitted by the tenderers.






2<sup>nd</sup> phase

Submission of proposals and negotiation



# MAIN LINE CONSTRUCTION PROCUREMENT TARGET TIME SCHEDULE





#### TO BE PROVIDED BY EMPLOYER

#### **Land Acquisition**

May take up to 2 years depending on the acquisition process and ownership at starting of the procedure (State, Municipality or Private), thus difficult to predict precisely when land in a specific section would be available to start construction.

The procedure has started but calendar of availability of land will be known second half of 2022.

#### Approved detailed technical design

RB Rail AS is the contracting Authority for the Design of the main line, all contracts are signed and most of the sections are in between Value Engineering Phase and Master Design phase, due to the complexity of Latvian construction law, the high number of stakeholders and a number of Building permit sections in which mainline design is divided is difficult predict precisely when land in a specific section would be available to start construction.

In despite design works are progressing in every section precise and final calendar of delivery of approved Detailed Technical design will be available second half of 2022.



#### TO BE PROVIDED BY EMPLOYER

#### **Project funding**

It is expected, that project funding will be available in stages, and the contract conditions will be developed to suit this approach using principle of committed and conditional amount of contract Taking in consideration that beneficiaries can commit for an amount only when funding is secured making sure at each stage that works will be ordered only if full finance will be available





# MAIN LINE CONSTRUCTION WORKS CONTRACT CONDITIONS

Andrea Laudanna

Chief Engineer



## CONTRACTUAL PRINCIPLES AND MAIN STAKEHOLDERS

Contract administration will be based on the application of Latvian Construction and Procurement law with fairness, equilibrium, and independence.

Contract will be structured on principle of Phasing of Works:

- Accepted Contract Amount awarded amount (for example 400 MEUR);
- Committed Contract Amount committed amount at starting of works (for example 100 MEUR) the part
  of the accepted contract amount that is committed at the signing of Contract or step by step
  activated at confirmation of the availability of funds;
- Accepted contract amount will reflect offer of the bidder for performing all works subject of the contract;
- On the basis of availability of funds, approved Detailed Technical Design, and availability of Land, Contracting authority and Beneficiary will commit in compensating works in specifically defined 6 months in advance section with a contractual obligation to warrantee a regular wealthy and financially sustainable progress of work for Contractor.



## CONTRACTUAL PRINCIPLES AND MAIN STAKEHOLDERS

#### Main Project Legal stakeholders

- **FIDIC Engineer:** will administrate the construction contract on behalf of the Contracting authority and perform Construction Supervision Works;
- Author supervisor: will perform Author Supervision during the Construction as defined by Latvian construction law;
- Public stakeholders: municipalities, utility owners, state forest, etc.;
- NoBo: Independent party for verification of application TSI requirements. Contracted to CERTIFIER S.A.;
- AsBo: Independent party appointed to assess the application of the hazard management safety risk process applied during a project. Contracted to CERTIFIER S.A.
- RB Rail AS: coordinator and manager of design, etc.;



#### PLANNED CONTRACTS OVERVIEW

Parties of the Contract:

Employer: SIA EDZL on the base of delegation Agreement signed by Ministry of Transport of Latvia; Construction Contract: FIDIC Red Book 2017 edition 2; Contract delivery in 2 phases – see slide No. 14 ECI; Engineer's Contract: FIDIC White Book 2017 edition 5.

- Pricing basis: unit prices divided in manpower, tolls and material components equivalent to Contractor direct
  costs will be the base of contract BoQs with escalation factors for labour, materials, plant & equipment for
  construction works; on top will be included overheads and profit as a pre-agreed percentage of direct costs to
  cover general overheads, site running facilities, project and construction management;
- Payment procedure: payment approved monthly by Engineer compensated on the base of actual measured quantities on the base of precisely defined method of measurement;
- Material procured by Contracting authority: Railway materials such as cable ducts, rails, ballast, sleepers, turnouts, will be procured by RBR and delivered to the Contractor. Materials call-off/handling procedure will be defined in the Construction Contract;
- Early contractor involvement: the contractor will be involved in the last phase of preparation of Detailed Technical design.



#### **EXAMPLE OF EDZL CONTRACT APPROACH**

**Defect Notification Period**: 5 years

Liability limitation: Under evaluation

Language of contract: English

Dispute arbitration Appointed permanent

**/avoidance:** or ad hoc DAAB

Payment terms: Generally, 30 days after receipt of IPC signed by Engineer

Applicable Laws: Latvian

Latvian national courts



#### PRINCIPLES OF EARLY CONTRACTOR INVOLVEMENT

The Construction Contractor planned to engage in an early cycle of the project while detailed engineering and land acquisition process is ongoing.

#### Contract delivery is divided into 2 phases both remunerated:

- 1. Planning: Constructability, Execution Plans, and Detailed Scheduling of the Works
- 2. Execution: Preform the Work to the Plans developed in Phase 1

#### Deliverables for Phase 1 - Planning:

- Prepare Level 3 In-depth Construction Driven Schedule
- Prepare Detail Construction Organization
- Perform Constructability reviews based upon the status of Engineering
- Prepare in Depth Logistics Management Plan complete with Warehousing and Laydown areas
- Prepare Temporary facilities/utilities plan, including identification of proposed work bases, parking craft areas and land requirements
- IMF facility development



#### PRINCIPLES OF EARLY CONTRACTOR INVOLVEMENT

- Review and input to building permits to ensure they comply with proposed construction methodology;
- Partial handover approach and how to allow other contractors to access the site prior to completion;
- Stakeholder and PR management plan, including how they will keep stakeholders informed, hotlines for the
  public to call to report issues, community engagement during construction etc.;
- Bill of Quantity review report;
- Solution on carbon impact greener methods of execution, etc.



#### TECHNICAL SPECIFICATION EXAMPLE







REINFORCEMENTS

#### DEFINITION

Steel reinforcing for cast in situ concrete

#### DESCRIPTION

Steel reinforcing for cast in situ concrete for concrete structure such as foundations, piers, abutment and walls, slabs, beams and where defined in structural detailed drawings:

This section has to be read in conjunction to the previous specification "Cast in situ concrete", the following specification "Formworks" and Structural drawings.

#### MATERIAL

#### STEEL REINFORFING FOR CAST IN SITU CONCRETE

The steel reinforcing S500 for cast in situ concrete is characterized by the following nominal values of the

Features	Requirments	Fractile (%) 5.0		
Characteristic yield stress f <sub>yk</sub>	≥ f <sub>ynom</sub>			
Characteristic breaking stress ft <sub>k</sub>	≥ f <sub>tnom</sub>	5.0		
(f <sub>t</sub> /f <sub>y</sub> ) <sub>k</sub>	≥1.15	10.0		
	<1.35			
( f <sub>t</sub> / f <sub>ynom</sub> ) <sub>k</sub>	≤1.25	10.0		
Elongation ( A <sub>gt</sub> ) <sub>k</sub> :	≥7.50%	10.0		
Spindle Diameter for bending tests to 90° and				
following straightening without cracks:				
Φ<12 mm	4 Φ			
12≤ Φ≤16 mm	5 Φ			
16≤ Φ≤25 mm	8 Φ			
25≤ Φ≤40 mm	10 Φ			

#### **ELECTRO-WELDED MESHES AND TRAILERS**

The steel of the welded mesh and lattice girders must be weldable.

The spacing of the bars must not exceed 330 mm.

The trusses are reticular components composed of bars and assembled by welding: For meshes and lattice made of S500 steel, the basic elements must have a diameter Ø that respects the limitation:

 $6 \text{ mm} \leq \emptyset \leq 16 \text{ mm}$ .

The ratio between the diameters of the mesh components and lattice bars must be:  $\emptyset \min I \emptyset \operatorname{Max} > 0.6$ 



Compone nt/ Task	Denig n Phase	Productio n Center	Documen £Type	Wes Senen	Progressive number of WBS	Part of WBS Element	Document Number		
18	В	0.1	8P	IF	00	0	0	0	2

**DEFINITION** DESCRIPTION **MATERIAL APPLICABLE REGULATIONS:** MATERIAL'S CHARACTERISTICS AND CONDITION OF SUPPLY **EXECUTION PROCEDURES CERTIFICATIONS, SAMPLES AND TESTS QUALITY ASSESSMENT -ACCEPTANCE CRITERIA MEASUREMENT CRITERIA** 



### BILL OF QUANTITY EXAMPLE FOLLOWING LATVIAN STANDARD LBN 501-17

								Vienība cen	a / Unit pricing					Kopējā cena / Total į	pricing	
Izmaksu pozīcija / Cost position	Specifik. Nr / Specs No.	Title of work	Rasējuma Nr. / Drawings No.	Mērvienība / Unit of measure	Darba daudzums / Quantity	Laika norma (c/h) / Time norm (m/h)	Darba samaksas likme* (euro/h) / Hourly rate* (euro/h)	Darba alga / Salary	Būvizstrādājum i / Materials	Mehānismi / Tools	Kopā / Total unit rate (euro)	Darbietilpība (c/h) / Total work (m/h)	Darba alga / Salary	Būvizstrādājumi / Materials	Mehānismi / Tools	Kopējā izmaksa EUR / Total in EUR
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17
5	DZELZCEĻA SLIEŽU CEĻI, ZEMES KLĀTNE, GARENPROFILI UN ŠĶĒRSPROFILI,  ÜDENSNOVADE / RAILWAY TRACKS, ROADBED, LONGITUDINAL PROFILES AND  CROSS SECTIONS, DRAINAGE  Kopā / Total: -										- €					
5.1.	ļ	zbērums / Railway embankment														
5.1.1	3	Earthworks		N/A												
5.1.1.1	EM-01, EM- 02	Top soil removing, thickness 0.3m	SC-25, SC-29 / SC-48	m <sup>3</sup>	39,998.70							- €	- €	- €	- €	- €
5.1.1.2	02 EM-U1, EM-	Excavation under top soil (included service road, fence, ditches,) plus transportation and storage	SC-25, SC-29 / SC-48	m³	82,002.70							- €	- €	- €	- €	- €
5.1.2		Embankments		N/A												
5.1.2.1		Compaction of subgrade (foundation of embankment) after removing topsoil	SC-25, SC-29 / SC-48	m²	133,093.60							- €	- €	- €	- €	- €
5.1.2.2	EM-01, EM- 04	Non-woven geotextile, CBR > 3.0 kN, T > 10/10kN/m	SC-25, SC-29 / SC-48	m <sup>2</sup>	141,287.40							- €	- €	- €	- €	- €
5.1.2.3	03	Base of foundation - granular crushed filling, fr.0/63mm, thickness 0.7m, compaction roller, 1 layer max. 0.3m	SC-25, SC-29 / SC-48	m³	90,095.60							- €	- €	- €	- €	- €
5.1.2.4	02	Replacement of excavated peat - granular filling	SC-25, SC-29 / SC-48	m <sup>3</sup>	18,444.40							- €	- €	- €	- €	- €
5.1.2.5	03	Embankment - filling material + compaction	SC-25, SC-29 / SC-48	m <sup>3</sup>	358,569.90							- €	- €	- €	- €	- €
5.1.2.6	03	Prepared subgrade, thickness 50cm	SC-25, SC-29 / SC-48	m <sup>3</sup>	25,158.70							- €	- €	- €	- €	- €
5.1.2.7	EM-01, EM- 03	Sub-ballast, thickness 32cm	SC-25, SC-29 / SC-48	m <sup>3</sup>	14,865.90							- €	- €	- €	- €	- €
5.1.2.8	EM-01, EM- 03	Protecting layer	SC-25, SC-29 / SC-48	m <sup>3</sup>	4,238.80							- €	- €	- €	- €	- €
5.1.2.9		Final treatment of embankments to its required slopes	SC-25, TS-L-01, TS-L-02	m²	42,284.60							- €	- €	- €	- €	- €
5.1.2.10		Sowing of agricoltural land or slopes with grassing hydro-seeding	SC-25, TS-L-01, TS-L-02	m2	42,633.00							- €	- €	- €	- €	- €
5.1.2.11	EM-05	Supply and planting of shrubs		each	1,697.00							- €	- €	- €	- €	- €

KOPĀ / TOTAL = Virsizdevumi / Overhead cost = Pelna / Profit = KOPĀ BEZ PVN / TOTAL WITHOUT VAT =

Unit Pricing - the unit price that will be filled by bidder following above split as for requirement of Latvian construction and procurement law

### EDZL

# DZL MAIN BUSINESS DECISION TO BE TAKEN BY CONTRACTING AUTHORITY ON BASE OF RESULT OF ANALYSIS OF QUESTIONNAIRE FILLED BY MARKET ACTORS

### Procurement qualification requirements?

Previous experience in open line railway construction, turnover for railway construction, employed construction management personnel, certification, BIM experience, etc

#### 2 sections for construction works?

To divide construction works and procurement object in 2 section of average ~125 km

#### Vertical separation of construction works?

Substructure (earth work, embankment construction, under and overpasses, bridges, etc.).

Rail and ballast laying in separate

procurement.

## Point Type objects designed under EDZL responsibility to be include in contract?

 IMFs Skulte and lecava - also can be used asconstruction base – lecava for South section and Skulte for North section;
 2) 12 regional stations platforms, overpass and buildings:

#### Contract conditions?

Payment term process, advance payment amount, liability limitation, insurance, dispute resolution, etc.

Decision will be based on analysis of response given by market actors to questionnaire submitted with invitation to this event by EDZL/RB Rail



# MAIN LINE CONSTRUCTION WORKS OVERVIEW OF THE TASK

#### Einārs Jaunzems

Head of Project Implementation Department



#### MAINLINE CHARACTERISTICS IN LATVIA

Mainline total length	255 km
Railway bridge	60
<ul> <li>Road overpass</li> </ul>	85
<ul> <li>Animal passage</li> </ul>	9
<ul> <li>Construction of</li> </ul>	12
Regional station (optional)	
<ul> <li>IMF (optional)</li> </ul>	2
<ul> <li>Prepared subgrade</li> </ul>	4 Millions m <sup>3</sup> ;
<ul> <li>Embankments</li> </ul>	12 Millions m³;
<ul> <li>Cutting</li> </ul>	2 Millions m³;
<ul> <li>Sub-ballast</li> </ul>	1 Millions m³;
<ul> <li>Ballast construction</li> </ul>	1 Millions m³;
<ul> <li>Rail instalation works</li> </ul>	71 000 t;
	(consolidated procurement of materials done by RBR)
<ul> <li>Concrete</li> </ul>	263 000 m <sup>3</sup> ;

Mainline construction does not include construction works in Riga city.





## CONSTRUCTION WORKS IN SECTIONS WILL BE ORGANIZED BY BUILDING PERMITS



### LVDS4 - Misa-LV/LT border Main parameters

- 45 km long
- 4 railway bridges
- 16 road viaducts
- 1 animal crossing
- 4 railway viaducts

DESIGN SECTION	SECTION TOTAL BUILDING PERMITS
LVDS1 - Upeslejas-Rīga-Misa (56 km)	20
LVDS2 - Vangaži – Salaspils – Misa (67 km)	31
LVDS3 – EE/LV border - Vangaži (94 km)	14
LVDS4 - Misa-LV/LT border (45 km)	11
TOTAL	76



## CONSTRUCTION WORKS IN SECTIONS WILL BE ORGANIZED BY BUILDING PERMITS




### Building permits of first section where works can be started

#### LVDS4 - Misa-LV/LT border

- BP 1 / 4-1 Mainline lecavas Passing Loop (147+000 152+000)
- BP 2 / 4-1 LDZ Railway Crossing section (152+000 -156+000)
- BP 3 / 4-1 lecava RB Station section (156+000 157+000)
- BP 4 / 4-2 lecava River Bridge section (157+000 158+000)
- BP 5 / 4-1 lecava South Section (158+000 165+665)
- BP 6 / 4-3 Bauska North section (165+665 176+300)
- BP 7 / 4-4 Memele River Bridge section (176+300 177+600)
- BP 8 / 4-3 Bauska Station section (177+600 182+000)
- BP 9 / 4-3 Bauska South section (182+000 188+600)
- BP 10 / 4-5 Ceraukste section (188+600 190+000)
- BP 11 / 4-5 Lithuanian border section (190+000 192+134)

#### **EXAMPLE OF CONSTRUCTION SECTION** FROM RIX TO OLAINE MUNICIPALITY BORDER (DESIGN SECTION LVDS1 DSP3)



Section length – 24,67 km; Building permits – 7;

Regional stations - 3; Railway bridges/viaducts - 7; Pergola crossing – 1; Overpass road - 9;

Underpass road - 1; Ecoducts - 3;



## RELATED OBJECT DESIGN/CONSTRUCTION STATUS

Type of object	Name of object	Progress status		Author of design	Main contractor	Engineer	
		Design	Construction	Amount of contract signed/committed	Amount of contract	Amount of contract	
	Riga central train station (+ Daugava railway bridge)	Ongoing (FIDIC Yellow book)		BERERIX (Signed 430 538 203 EUR)		EGIS&DB (23 959 441 EUR)	
Point - - -	RIX (airport) train station	Completed	Ongoing (FIDIC Red book)	General Partnership PROSIV (4 545 774 EUR + Author supervision 864 864 EUR)	B.S.L.Infra (Signed 236 961 150 EUR)	Prointec&Forma2 (5 849 797 EUR)	
	Salaspils FHT	Ongoing	-	-	-	-	
	IMFs Skulte and lecava	Procurement phase	-	-	-	-	
	Regional Stations (17 buildings)	Procurement phase	-	-	-	-	



























## RELATED OBJECT DESIGN/CONSTRUCTION STATUS

Type of object	Name of object	Progress status		Author of design	Main contractor	Engineer
		Design	Construction	Amount of contract signed/committed	Amount of contract	Amount of contract
System	Rolling depo Jaunmarupe	PRE Procurement phase	-	-	-	-
Rural mainline	LVDS1 - Upeslejas-Rīga-Misa (section length 56 km)	Ongoing Master design  Estimated completion End of 2022	PRE procurement phase (FIDIC Red book)	IDOM-INECO (12 989 200 EUR)	PRE procurement phase	PRE procurement phase
	LVDS2 - Vangaži – Salaspils – Misa (section length 67 km)			EGIS & DB CONSULTING (12 024 529 EUR)		
	LVDS3 – EE/LV border - Vangaži (section length 94 km)			Cons. Ingeniería y Economía del Transporte S.M.E. M.P. S.A. and Ardanuy Ingeniería S.A (13 523 414 EUR)		
	LVDS4 - Misa-LV/LT border (section length 45 km)	-		IDOM, CONSULTING, ENGINEERING,ARCHITECTURE S.A.U. (6 903 802 EUR)		













## TYPICAL TIMELINE FOR SECTION CONSTRUCTION WORKS

Construction work phase	Date
Preparatory work	
Approval of Detailed technical design in section	End of 2022
Finished land acquisition in section	End of 2022
Construction works	
End of procurement process. Signing of agreement and mobilization	March 2023
Start of early construction contractor involvement phase	April 2023
Receiving permit to start construction works (BUN)	April 2023
Site office installation	May 2023
Start of construction works	May 2023
End of construction works	TBD
Systems construction works	
Systems ENE+CSS construction works	
Defect notification period for systems, ENE, CSS construction works	



# EXAMPLE OF STRUCTURES TO BE BUILT

### Ēriks Diļevs

TECHNICAL DIRECTOR, AS RB Rail




#### **EMBANKMENT**

### Main parameters of the structure:

Height: 1.50m to 12.00m

Width: 12.00m

	E <sub>V2</sub> (DIN 18	8134)	D <sub>pr</sub> (EN 13286-2 standard Proctor)		
Layer	Target value	Testing frequency	Target value	Testing frequency	
Subballast	≥ 120 MPa	Once per 100 m	≥ 103%	Once per 20 m	
Prepared subgrade	≥ 80 Mpa (untreated material)	2 locations - beneath the	≥ 100%	2 locations - beneath the	
	≥ 120 Mpa (treated material)	railway and near the edge		railway and near the edge	
Upper embankment (embankment/excavate surface)	≥ 45 Mpa for fine soils ≥ 60 Mpa for sandy or gravelly soils ≥ 80 Mpa (treated material)		≥ 97 %		





#### **BRIDGES, ROAD OVERPASSES**

#### Main parameters of the structure:

- Precast or cast in situ
- Structural steel S355
- Concrete minimum strength requirements:
  - For span (superstructure): f'c 28 days = 45 MPa;
  - For pier cap, pier: f'c 28 days = 35 MPa;
  - For foundation: f'c 28 days = 30 MPa.
- Permanent loads (according to EN 1991-1-1):
  - Ballast (including sleeper)
     20.0 kN/m³

• 2 rails per track + fastening 1.5 kN/m/track


• 1 handrail on each side (2 units) 0. 7.0 kN/linear meter

	Code	Unit	Quantity
Concrete C45/55. Deck (beams)	1.2.1	m3	667,80
Concrete C45/55. Deck (slab)	1.2.1	m3	868,13
Concrete C30/37 transition slab	3.8.1	m3	365,00
Reinforcement steel 500MPa beams	1.3.2	kg	100.169,36
Reinforcement steel 500MPa slab	1.3.2	kg	130.219,35
Reinforcement steel 500MPa transition slab	1.3.2	kg	29.200,00
Prestressing reinforcement	1.3.3	kg	23.372,85
Post-tensioned steel 835/1030 mpa in bars		kg	0,00
Planks	1.1.8	m2	3.774,00
Deck formwork	1.1.4	m2	0,00
Parapet	1.4.6	m	0,00
Falsework (overpass)	1.3.8	m2	0,00
Launch of Deck T-beams	1.1.5	each	143,00

Deck for 26m long road overpass specification



### **BRIDGES, ROAD OVERPASSES**






#### **COMBINED ROAD/ANIMAL OVERPASS**

#### Main parameters of the structures:

- Total length: 66.0 m
- The width of structure: 22.0 m
- Traffic lane of gravel road: 7.5 m
- Animal walkway: 15.0 m



Combined Road/Animal crossing structure



#### **COMBINED ROAD/ANIMAL OVERPASS**








#### GAUJA RIVER BRIDGE NEAR MURJANI

#### Main parameters of the bridge:

- Multispan haunched reinforced concrete box girder
- Total length 1 400 m
- Total number of spans 25
- Central span width 110 m
- Central span height 7 m









## COMBINED BRIDGE OVER DAUGAVA RIVER NEAR SALASPILS

### Main parameters of the bridge:


- Total length 1150m
- 2+2 road carriageway
- 2 highspeed railway lines
- Steel truss girder with
  - 6 spans of 150m,
  - 2 spans of 125m
- Bottom chord height approx.12m over river level







## COMBINED BRIDGE OVER DAUGAVA RIVER NEAR SALASPILS






#### COMBINED BRIDGE OVER DAUGAVA RIVER

#### Specific parameters of the bridge:


- The bridge deck carries at top chord level a carriageway (4 traffic lanes), and at bottom chord level a high speed two track railway line 12.10m wide
- At top chord level, steel cantilevers are disposed transversely to provide the required transverse clearance, and a reinforced concrete slab provides the support for the road carriageway







#### COMBINED BRIDGE OVER DAUGAVA RIVER





#### **NOISE BARRIER**





# THANK YOU FOR ATTENTION!

We are ready to answer any questions.

<u>edzl@edzl.lv</u> <u>Gatis.gangitis@edzl.lv</u>







Ģenerāļa Radziņa krastmala 9 Rīga, LV- 1050

